



- NOTES:
1. MIN 2% SLOPE TO CITY CLEANOUT
 2. ALL GLUE JOINTS TO BE PURPLE PRIMER / HEAVY DUTY GRAY PVC CEMENT
 3. PIPING TO BE FREE OF EARTH & DEBRIS & INSPECTED BY CITY UTILITY W/ FOAM TEST BALL PRIOR TO CONNECTION & BACKFILL.
 4. FINAL SEWER CONNECTION SHALL NOT BE COMPLETED UNTIL TCO/OR CO IS IMMINENT AND INSPECTED & BY THE CITY UTILITY DEPT.

SEWER CONNECTION
CITY OF MARATHON -TYPICAL
 NOT TO SCALE